
# Attachment-7 Proposed Zoning and Details (2023) - 20790



# **Attachment-7 (continued)**

### "Specialized Low Density Residential" RL.4-22 Zone

In accordance with Part C (General Provisions and Parking) and Section 6 (Residential Zones) with the following site-specific exceptions:

#### Maximum Density (units/ha)

• Notwithstanding Table 6.17, the maximum density shall be 60 units per hectare.

#### Maximum Building Coverage (% of lot area)

Notwithstanding Table 6.18, the maximum Building Coverage shall be 32%

#### **Private Amenity Area - Cluster Townhouses**

• Notwithstanding Table 6.18, footnote 11.b.c., private amenity area for cluster townhouses may be setback 0 metres from the rear lot line in the RL.4-22 zone.

#### **Private Amenity Area – Stacked Townhouses**

- Notwithstanding Table 6.18, footnote 12 and 13, the following provisions apply to private amenity areas for stacked townhouses in the RL.4-22 zone.
  - a) private amenity areas for ground level units in stacked townhouses shall be a minimum of 10m2/unit and may be located in a front yard or an unclosed porch or balcony with no privacy screen.
  - b) Private amenity area for units above or below finished grade shall have a minimum of 6.5m2 and may be located in a front yard.
  - c) Private amenity areas for units above-grade must consist of a balcony and be defined by a wall or railing between adjacent units to a height of 1.8m.
  - d) Private amenity areas may face a public street

## Lot area per dwelling unit

 Notwithstanding Table 6.19, the minimum lot area per dwelling unit shall be 169m2 for the RL.4-22 zone.

#### **Exterior Side and Read Yard from a Private Street**

 Notwithstanding Table 6.19, front, exterior side and rear yard setbacks to private streets back of curb or sidewalk or lot line do not apply, for the RL.4-22 zone.

#### **Building Length**

Notwithstanding Table 6.19, the maximum building length shall be 60 metres.

# **Bicycle Parking Rates**

 Notwithstanding Section 5.8, bicycle parking requirements shall be 1 per stacked townhouse dwelling unit.

### **Electric Vehicle Parking Requirements**

 Notwithstanding Section 5.9, electric vehicle parking requirements shall not apply.